GENERAL NOTES: LEGEND: <u>GENERAL</u> WORK SHOWN HEREON SHALL BE DONE IN ACCORDANCE WITH THE "STANDARD CIVIL LIMITS OF WORK SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION," LATEST EDITION AND SUPPLEMENTS, THE CALIFORNIA BUILDING CODE (EXCAVATION AND GRADING), SHEET MATCH LINE AND CITY OF LENNOX LOCAL ORDINANCES AS APPLICABLE. 2. ALL GRADING WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE **ANNOTATION** REQUIREMENTS AND RECOMMENDATIONS CONTAINED IN THE GEOTECHNICAL REPORT, "[REPORT NAME]", BY [COMPANY NAME] DATED [MONTH DAY, YEAR]. 100.00 XX SURFACE ELEVATION/UTILITY ELEVATION 3. EXISTING TOPOGRAPHY SHOWN HEREON WAS TAKEN FROM A SURVEY DATED (100.00)XX EXISTING SURFACE ELEVATION/UTILITY ELEVATION DECEMBER 14, 2018 BY KPFF CONSULTING ENGINEERS. XX CONSTRUCTION NOTE 4. THE CONTRACTOR SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR THE JOB SITE CONDITIONS, INCLUDING SAFETY OF ALL PERSONS AND FLOW (DIRECTION AND GRADE) 2.0% PROPERTY, DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY, AND SHALL NOT BE LIMITED TO NORMAL WORKING HOURS. SLOPE (DIRECTION AND RUN:RISE) 5. PRIOR TO COMMENCING CONSTRUCTION, THE CONTRACTOR SHALL VERIFY ALL HORIZONTAL CONTROL POINT LABEL JOIN CONDITIONS FOR GRADING, DRAINAGE AND UNDERGROUND FACILITIES INCLUDING LOCATION AND ELEVATION OF EXISTING UNDERGROUND FACILITIES CURVE DATA LABEL AT CROSSINGS WITH PROPOSED UNDERGROUND FACILITIES. IF CONDITIONS DIFFER FROM THOSE SHOWN ON THE PLANS, THE CONTRACTOR SHALL NOTIFY PAD/FINISHED FLOOR ELEVATION |FF=100.00| THE ENGINEER AND SHALL NOT BEGIN CONSTRUCTION UNTIL THE CHANGED CONDITIONS HAVE BEEN EVALUATED. 6. ALL DRAWINGS ARE CONSIDERED TO BE A PART OF THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REVIEW AND COORDINATION OF ALL DRAWINGS AND SPECIFICATIONS PRIOR TO THE CURB/BACK OF CURB/GUTTER START OF CONSTRUCTION. ANY DISCREPANCIES THAT OCCUR SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO THE START OF RETAINING WALL/SITE WALL CONSTRUCTION SO THAT A CLARIFICATION CAN BE ISSUED. ANY WORK PERFORMED IN CONFLICT WITH THE CONTRACT DOCUMENTS OR ANY CODE PROPERTY LINE/RIGHT OF WAY REQUIREMENTS SHALL BE CORRECTED BY THE CONTRACTOR AT THEIR OWN EXPENSE AND AT NO EXPENSE TO THE OWNER OR ARCHITECT. CENTER LINE 7. THE ENGINEER PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ALL CHANGES TO THE PLANS MUST BE IN WRITING AND MUST BE APPROVED BY / / / / TO BE DEMOLISHED THE PREPARER OF THESE PLANS. 8. NOTES AND DETAILS ON DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE GIVEN, CONSTRUCTION **EROSION CONTROL** SHALL BE AS SHOWN FOR SIMILAR WORK. SANDBAGS ∞ 9. THE EXISTENCE, LOCATION AND CHARACTERISTICS OF UNDERGROUND UTILITY INFORMATION SHOWN ON THESE PLANS HAVE BEEN OBTAINED FROM A REVIEW OF AVAILABLE RECORD DATA. NO REPRESENTATION IS MADE AS TO THE ACCURACY OR COMPLETENESS OF SAID UTILITY INFORMATION. THE CONTRACTOR PROPOSED BUILDING EXCAVATION OUTLINE SHALL TAKE PRECAUTIONARY MEASURES TO PROTECT THE UTILITY LINES SHOWN AND ANY OTHER LINES NOT OF RECORD OR NOT SHOWN ON THESE EXISTING DRAINAGE DIRECTION OF FLOW IF AT ANY TIME DURING GRADING OPERATIONS, ANY UNFAVORABLE GEOLOGICAL PROTECT TREE IN PLACE CONDITIONS ARE ENCOUNTERED, GRADING IN THAT AREA WILL STOP UNTIL APPROVED CORRECTIVE MEASURES ARE OBTAINED. 11. THE PROPOSED GRADE IS THE FINAL GRADE AND NOT THE ROUGH GRADE. THE CONTRACTOR SHALL SUBTRACT THE THICKNESS OF THE PAVED SECTION <u>GRADING</u> AND/OR LANDSCAPE TOPSOIL SECTION TO ARRIVE AT THE ROUGH GRADE PROPOSED MAJOR CONTOUR ELEVATION. 12. STRAIGHT GRADE SHALL BE MAINTAINED BETWEEN CONTOUR LINES AND SPOT PROPOSED MINOR CONTOUR ELEVATIONS UNLESS OTHERWISE SHOWN ON THE PLANS. $\longrightarrow \longrightarrow \longrightarrow \longrightarrow \longrightarrow \longrightarrow$ 13. ALL DEBRIS AND FOREIGN MATERIAL SHALL BE REMOVED FROM THE SITE AND DISPOSED OF AT APPROVED DISPOSAL SITES. THE CONTRACTOR SHALL OBTAIN GRADE BREAK LINE NECESSARY PERMITS FOR THE TRANSPORTATION OF MATERIAL TO AND FROM RIDGE LINE THE SITE. _____R___ 14. ALL FILL SOILS OR SOILS DISTURBED OR OVEREXCAVATED DURING $\overline{} \longrightarrow \longrightarrow \longrightarrow \longrightarrow \longrightarrow \longrightarrow$ EARTHEN SWALE CONSTRUCTION SHALL BE COMPACTED PER THE REQUIREMENTS OF THE SOILS REPORT BUT NOT LESS THAN 90% MAXIMUM DENSITY AS DETERMINED BY SAWCUT ____ A.S.T.M. SOIL COMPACTION TEST D-1557. LIMITS OF GRADING 15. THE CONTRACTOR SHALL OBTAIN AN O.S.H.A. PERMIT FROM THE CALIFORNIA DIVISION OF INDUSTRIAL SAFETY PRIOR TO THE CONSTRUCTION OF TRENCHES GRADING BENCH OR EXCAVATIONS WHICH ARE FIVE FEET OR DEEPER. GRADED SLOPE (HORIZONTAL: VERTICAL) 16. DIMENSIONS TO PIPELINES ARE TO CENTERLINE UNLESS OTHERWISE NOTED. 17. ALL WATER LINES SHALL BE INSTALLED WITH 36" MINIMUM COVER FROM TOP OF PIPE TO FINISHED GRADE, UNLESS OTHERWISE NOTED. 18. THRUST BLOCKS SHALL BE INSTALLED AT WATERLINE HORIZONTAL AND VERTICAL BENDS, TEES, CAPPED ENDS AND REDUCERS ACCORDING TO THE SANITARY SEWER DETAILS PROVIDED ON THESE PLANS. 20. CONSTRUCTION STAKING FOR IMPROVEMENTS SHOWN ON THESE PLANS SHALL BE PERFORMED BY A LICENSED LAND SURVEYOR. CONSTRUCTION STAKING DOMESTIC WATER SURVEYOR SHALL BE RESPONSIBLE FOR COORDINATION OF THESE PLANS WITH SOURCE DRAWINGS PREPARED BY ARCHITECT, LANDSCAPE ARCHITECT, FIRE WATER STRUCTURAL ENGINEER, MEP CONSULTANT AND ANY OTHER DISCIPLINE PRIOR TO START OF STAKING AND CONSTRUCTION. ANY DISCREPANCIES THAT OCCUR STORM DRAIN SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO THE START OF CONSTRUCTION SO THAT A CLARIFICATION CAN BE ISSUED. GAS 21. THE CONTRACTOR SHALL REPLACE ALL EXISTING IMPROVEMENTS DAMAGED DURING CONSTRUCTION TO MATCH EXISTING, INCLUDING PERMANENT TRENCH TELEPHONE PERFORATED PIPE 22. CONTRACTOR TO CONTACT UNDERGROUND SERVICE ALERT (800-227-2600) PRIOR TO EXCAVATION. POINT OF CONNECTION 23. ALL DIMENSIONS ARE IN FEET OR DECIMALS THEREOF. COORDINATION POINT 24. ALL CURB DIMENSIONS AND RADII ARE TO PAVEMENT FACE OF CURB. CAP OR PLUG 25. CONTRACTOR TO BE AWARE OF ALL OVERHEAD LINES AT ALL TIMES, SO AS UTILITY MANHOLE NOT TO DISTURB THEM. 26. WATER SHALL BE PROVIDED ONSITE AND USED TO CONTROL DUST DURING UTILITY CLEANOUT CONSTRUCTION OPERATIONS. STORM DRAIN INLET 27. CONTRACTOR SHALL OBTAIN ANY NECESSARY PERMITS FROM THE CITY OF LENNOX FOR ALL WORK WITHIN THE PUBLIC RIGHT-OF-WAY. AREA DRAIN/PLANTER DRAIN 28. STORM DRAINAGE SYSTEMS SHOWN ON THESE PLANS HAVE BEEN DESIGNED TRENCH DRAIN FOR THE FINAL SITE CONDITION AT COMPLETION OF THE PROJECT. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ADEQUATE DRAINAGE OF THE FIRE HYDRANT SITE, DURING INTERIM CONDITIONS OF CONSTRUCTION. THRUST BLOCK 29. CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS, INCLUDING NPDES, FROM THE APPROPRIATE JURISDICTIONAL AGENCIES FOR DISCHARGE OF FIRE DEPARTMENT CONNECTION (FDC) GROUNDWATER THAT MAY BE NECESSARY TO ACCOMPLISH EXCAVATIONS SHOWN ON THESE PLANS. POST INDICATOR VALVE (PIV) WATER VALVE

BACKFLOW ASSEMBLY

UTILITY METER VAULT

AC	ASPHALTIC CONCRETE	МН	MANHOLE
BCR	BEGIN CURVE RETURN	(N)	NORTH
BW	BACK OF WALK	NTS	NOT TO SCALE
BLDG	BUILDING	PA	PLANTER AREA
ВМ	BENCH MARK	POC	POINT OF CONNECTION
BOS	BOTTOM OF STAIRS	PIV	POST INDICATOR VALVE
ВМР	BEST MANAGEMENT PRACTICES	PCC	POINT OF COMPOUND CURVE
СВ	CATCH BASIN	PRC	POINT OF REVERSE CURVE
CI	CAST IRON	PRV	PRESSURE REDUCING VALVE
CL	CENTER LINE	PVC	POLYVINYL CHLORIDE
CMU	CONCRETE MASONRY UNIT	R	RADIUS
CO	CLEANOUT	RCIP	RECTANGULAR CAST IRON PIF
CONC	PORTLAND CEMENT CONCRETE	RD	ROOF DRAIN
CF	CURB FACE	RW	RIGHT-OF-WAY
DW	DOMESTIC WATER	(S)	SOUTH
(E)	EAST	S=	SLOPE EQUALS
ECR	END CURVE RETURN	SD	STORM DRAIN
EG	EDGE OF GUTTER	SSMH	SANITARY SEWER MANHOLE
EL. OR ELEV	ELEVATION	SS	SANITARY SEWER
ELEC	ELECTRIC, ELECTRICAL	STD	STANDARD
EX. OR EXIST.	EXISTING	SDMH	STORM DRAIN MANHOLE
FDC	FIRE DEPARTMENT CONNECTION	TC	TOP OF CURB
FF	FINISHED FLOOR	TEL	TELEPHONE
FG	FINISHED GRADE (LANDSCAPE)	TG	TOP OF GRATE
FS	FINISHED SURFACE (HARDSCAPE)	TOS	TOP OF STAIRS
FH	FIRE HYDRANT	TW	TOP OF WALL
FL	FLOW LINE	TS	TRAFFIC SIGNAL
FT	FOOT OR FEET	TSB	TRAFFIC SIGNAL BOX
FU	FIXTURE UNITS	TYP	TYPICAL
FW	FIRE WATER	TV	TELEVISION
GPM	GALLONS PER MINUTE	VIF	VERIFY IN FIELD
GV	GATE VALVE	VLT	VAULT
HDPE	HIGH DENSITY POLYETHYLENE	VCP	VITRIFIED CLAY PIPE
HP	HIGH POINT	(W)	WEST
INV.	INVERT	W	WATER
LP	LOW POINT	WM	WATER METER
MAX.	MAXIMUM	WV	WATER VALVE
MIN.	MINIMUM		

ABBREVIATIONS:

PATTERN LEGEND:

CONCRETE PAVING

(REFER TO SHEET C5.0 FOR DETAILS)

(REFER TO SHEET C5.0 FOR DETAILS)

PLANTER AREA/LANDSCAPE

(REFER TO ARCHITECTURAL PLANS FOR DETAILS)

(REFER TO LANDSCAPING PLANS FOR DETAILS)

THIS PLAN HAS BEEN REVIEWED AND CONFORMS TO RECOMMENDATIONS

OF SOILS ENGINEERING/GEOLOGICAL REPORT BY [COMPANY NAME] DATED


DATE


STAMP

[MONTH DAY, YEAR].

SIGNATURE

SHEET INDEX: CIVIL DRAWINGS CO.1 TITLE SHEET SURVEY (FOR REFERENCE ONLY) C1.1 DEMOLITION PLAN EROSION CONTROL PLAN GRADING PLAN C1.4 UTILITY PLAN PAVING PLAN C5.0 CIVIL DETAILS






DAYS BEFORE YOU DIG

1-800-227-2600 CALL USA/SC FOR UNDERGROUND LOCATING 48 HOURS BEFORE YOU

IMPORTANT NOTICE SECTION 4216/4217 OF THE GOVERNMENT CODE REQUIRES A DIGALERT IDENTIFICATION NUMBER BE ISSUED BEFORE A "PERMIT TO EXCAVATE" WILL BE VALID. FOR YOUR DIGALERT I.D. NUMBER CALL UNDERGROUND SERVICE ALERT


TOLL FREE 1-800-227-2600 TWO WORKING

integrated design construction management sustainability



700 South Flower Street Suite 2100 Los Angeles, CA 90017 O: 213.418.0201 F: 213.266.5294 www.kpff.com

TITLE SHEET




integrated construction management sustainability

700 South Flower Street Suite 2100 Los Angeles, CA 90017 O: 213.418.0201 F: 213.266.5294 www.kpff.com

SURVEY (FOR REFERENCE ONLY)

FOR REFERENCE ONLY



GENERAL DEMOLITION NOTES:

- 1. CONTRACTOR TO CLEAR PROJECT SITE AREA WITHIN THE CONFINES OF THE DEMOLITION LIMIT LINE. THE CONTRACTOR SHALL DEMOLISH AND REMOVE FROM THE SITE ALL EXISTING UTILITIES, STRUCTURES, PLANTERS, TREES, AND ALL OTHER SITE FEATURES, UNLESS OTHERWISE NOTED ON THE PLAN.
- 2. REMOVAL OF LANDSCAPING SHALL INCLUDE ROOTS AND ORGANIC MATERIALS.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY AND ALL PERMITS AND SHALL PAY ALL FEES NECESSARY FOR ENCROACHMENT, GRADING, DEMOLITION AND DISPOSAL OF SAID MATERIALS AS REQUIRED BY PRIVATE, LOCAL AND STATE JURISDICTIONS.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR A SITE INSPECTION TO FULLY ACKNOWLEDGE THE EXTENT OF THE DEMOLITION WORK.
- 5. THE CONTRACTOR SHALL VERIFY AND LOCATE ALL EXISTING ABOVE AND UNDERGROUND UTILITIES. LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATE AND ARE SHOWN FOR GENERAL INFORMATION ONLY.
- 6. DAMAGE TO ANY EXISTING UTILITIES AND SERVICES TO REMAIN SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR SHALL REPAIR AND/OR REPLACE IN KIND.
- 7. EROSION CONTROL MEASURES SHALL BE IMPLEMENTED TO PREVENT DEBRIS AND UNSUITABLE MATERIALS FROM ENTERING STORM DRAINS, SANITARY SEWERS AND STREETS.
- 8. DUST CONTROL SHALL BE IMPLEMENTED DURING DEMOLITION.
- 9. DEMOLITION IS LIMITED TO WITHIN DEMOLITION LIMIT LINE UNLESS NOTED OTHERWISE.
- 10. THE CONTRACTOR SHALL VERIFY THE LOCATION AND QUANTITY OF EXISTING SURFACE STRUCTURES AND SHALL BE SOLELY RESPONSIBLE FOR ANY UNIDENTIFIED UTILITIES, IMPROVEMENTS, TREES, ETC. TO BE DEMOLISHED AND REMOVED WITHIN THE DEMOLITION LIMIT LINE, INCLUDING APPURTENANT FOUNDATIONS OR SUPPORTS.
- 11. DEMOLITION CALLOUTS IN THIS SECTION ARE REPRESENTATIVE OF WHAT IS TO BE DONE, NOT AN ITEMIZED ACCOUNTING FOR EACH PIPE, CATCH BASIN, MANHOLE, VAULT, ETC. THAT IS TO BE DEMOLISHED, REMOVED AND DISPOSED

DEMOLITION NOTES:

PROTECT-IN-PLACE

- 1 PROTECT-IN-PLACE EXISTING CONCRETE PAVEMENT.
- 2 PROTECT—IN—PLACE EXISTING OVERHEAD UTILITIES.
- PROTECT-IN-PLACE EXISTING BLOCK WALL.
- 4 PROTECT-IN-PLACE EXISTING LANDSCAPE AREA.
- 5 PROTECT-IN-PLACE EXISTING TRANSFORMER AND PAD.
- 6 PROTECT-IN-PLACE EXISTING WROUGHT IRON FENCE.
- 7 PROTECT-IN-PLACE EXISTING GATE.
- 8 PROTECT-IN-PLACE EXISTING STRUCTURE.
- 9 PROTECT-IN-PLACE EXISTING STAIRCASE.
- 10 PROTECT-IN-PLACE EXISTING ASPHALT PAVEMENT.
- PROTECT-IN-PLACE EXISTING PULL BOX. ADJUST TO GRADE IF NEEDED.

DEMOLISH & REMOVE

- DEMOLISH & REMOVE PORTION OF EXISTING BUILDING. SEE SHEET A2.0 FOR CONTINUATION.
- 2 DEMOLISH & REMOVE EXISTING LANDSCAPE AREA.
- 3 DEMOLISH & REMOVE EXISTING CONCRETE PAVEMENT.
- 4 DEMOLISH & REMOVE EXISTING PLANTER.
- 5 DEMOLISH & REMOVE PORTION OF EXISTING CONCRETE WALL. SEE SHEET A1.1.
- 6 DEMOLISH & REMOVE EXISTING AC UNIT.
- 7 DEMOLISH & REMOVE PORTION OF EXISTING WROUGHT IRON FENCE. SEE SHEET A1.1.
- 8 DEMOLISH & REMOVE EXISTING FENCE.
- 9 DEMOLISH & REMOVE PORTION OF EXISTING LANDSCAPE AREA FOR PROPOSED DRIVEWAY WIDENING.
- DEMOLISH & REMOVE PORTION OF EXISTING CURB AND GUTTER FOR PROPOSED DRIVEWAY WIDENING.
- (11) DEMOLISH & REMOVE EXISTING DRIVEWAY.
- (12) DEMOLISH & REMOVE EXISTING TREE.

LEGEND:

LIMIT OF WORK

PROPERTY LINE

-/-/ DEMOLITION LINE

integrated design construction management sustainability



kpff

700 South Flower Street Suite 2100 Los Angeles, CA 90017 O: 213.418.0201 F: 213.266.5294 www.kpff.com

HELP EVERYONE
LENNOX CLINIC
223 FIRMONA AVE.
ENNOX, CA 90304

| drawn by | checked by | produced by | prod

PRESENTATION
STRUCTION DOCUMENTS
ECK SUBMITTAL

14/2018 DESIGN DEV 15/2019 FINISHES PR 11/2019 30% CONST 50% CONST 11/2019 PLAN CHECK -

42/14/20 61/29/20 62/15/20 63/11/20 -

DEMOLITION PLAN

C1.1

5' 10' |

STAGGERED 18**"**

CXXX N.T.S.

- 1. BAG MATERIAL: BAGS SHOULD BE WOVEN POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE FABRIC, MINIMUM UNIT WEIGHT OF 4 OUNCES/YD2, MULLEN BURST STRENGTH EXCEEDING 300 LB/IN2 IN CONFORMANCE WITH THE REQUIREMENTS IN ASTM DESIGNATION D3786, AND ULTRAVIOLET STABILITY EXCEEDING 70% IN CONFORMANCE WITH THE REQUIREMENTS IN ASTM DESIGNATION D4355.
- 2. BAG SIZE: EACH GRAVEL-FILLED BAG SHOULD HAVE A LENGTH OF 18 IN., WIDTH OF 12 IN., THICKNESS OF 3 IN., AND MASS OF APPROXIMATELY 33 LBS. BAG DIMENSIONS ARE NOMINAL, AND MAY VARY BASED ON LOCALLY AVAILABLE MATERIALS.
- 3. FILL MATERIAL: FILL MATERIAL SHALL BE 0.5 TO 1.0 INCH CRUSHED ROCK, CLEAN AND FREE OF CLAY, ORGANIC MATTER, AND OTHER DELETERIOUS MATERIAL, OR OTHER SUITABLE OPEN-GRADED, NON-COHESIVE, POROUS GRAVEL.
- 4. TURN THE ENDS OF GRAVEL BAG BARRIER UP SLOPE TO PREVENT RUNOFF FROM GOING AROUND BARRIER.
- 5. USE PYRAMID APPROACH WHEN STACKING BAGS.

GRAVEL BAG BARRIER

THAN 3" BUT SMALLER THAN 6" ORIGINAL **GRADE** - FILTER FABRIC 12" MIN. UNLESS OTHERWISE -SPECIFIED BY A SOILS ENGINEER **SECTION** 10'R GEOTEXTILE FILTER FABRIC CRUSHED AGGREGATE - CORRUGATED $(3^{\circ}-6^{\circ})$ DIA. STONE) STEEL PANELS 2 STABILIZED CONSTRUCTION ENTRANCE

CRUSHED AGGREGATE GREATER -

CXXX N.T.S.

CORRUGATED STEEL PANELS

- 1. THE CONSTRUCTION ENTRANCE ROADWAYS SHALL BE STABILIZED SO AS TO PREVENT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC ROADS. DEPOSITIONS MUST BE SWEPT UP IMMEDIATELY AND MAY NOT BE WASHED DOWN BY RAIN OR OTHER MEANS INTO THE STORM DRAIN SYSTEM.
- 2. STABILIZED CONSTRUCTION ENTRANCE SHALL BE LOCATED AT ANY POINT WHERE TRAFFIC WILL BE ENTERING OR LEAVING A CONSTRUCTION SITE OR FROM A PUBLIC RIGHT OF WAY, STREET, ALLEY, AND SIDEWALK OR PARKING AREA.
- 3. IF A WASH RACK IS INCLUDED, A SEDIMENT TRAP OF SOME KIND MUST ALSO BE PROVIDED TO COLLECT WASH WATER RUNOFF.
- 4. ALL VEHICLES ACCESSING THE CONSTRUCTION SITE SHALL UTILIZE THE STABILIZED CONSTRUCTION ENTRANCE.

STREET MAINTENANCE NOTES

- 1. REMOVE ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS IMMEDIATELY.
- 2. SWEEP PAVED AREAS THAT RECEIVE CONSTRUCTION TRAFFIC WHENEVER SEDIMENT BECOMES VISIBLE.
- 3. PAVEMENT WASHING WITH WATER IS PROHIBITED IF IT RESULTS IN A DISCHARGE TO THE STORM DRAIN SYSTEM

BMP NOTES:

THE FOLLOWING BMPS AS OUTLINED IN, BUT NOT LIMITED TO, THE BEST MANAGEMENT PRACTICE HANDBOOK, CALIFORNIA STORMWATER QUALITY TASK FORCE, SACRAMENTO, CALIFORNIA, JULY 2012, MAY APPLY DURING THE CONSTRUCTION OF THIS PROJECT (ADDITIONAL MEASURES MAY BE REQUIRED IF DEEMED APPROPRIATE BY CITY INSPECTORS):

EROSION CONTROL

EC1-SCHEDULING EC2-PRESERVATION OF EXISTING VEGETATION EC3-HYDRAULIC MULCH EC4 HYDROSEEDING EC5 SOIL BINDERS EC6-STRAW MULCH EC7-GEOTEXTILES AND MATS EC8-WOOD MULCHING EC9-EARTH DIKES AND DRAINAGE SWALES EC10 VELOCITY DISSIPATION DEVICES EC11 SLOPE DRAINS EC12-STREAMBANK STABILIZATION EC13-RESERVED EC14-COMPOST BLANKET EC15-SOIL PREPARATION/ROUGHENING

TEMPORARY SEDIMENT CONTROL

EC16-NON-VEGETATIVE STABILIZATION

SE1-SILT FENCE SE2-SEDIMENT BASIN SE3-SEDIMENT TRAP SE4-CHECK DAM SE5-FIBER ROLLS SE6-GRAVEL BAG BERM SE7-STREET SWEEPING AND VACUUMING SE8-SANDBAG BARRIER SE9-STRAW BALE BARRIER SE10-STORM DRAIN INLET PROTECTION SE11-ACTIVE TREATMENT SYSTEMS SE12-MANUFACTURED LINEAR SEDIMENT CONTROLS SE13-COMPOST SOCKS AND BERMS SE14-BIOFILTER BAGS

EQUIPMENT TRACKING CONTROL

TC1-STABILIZED CONSTRUCTION ENTRANCE/EXIT TC2-STABILIZED CONSTRUCTION ROADWAY TC3-ENTRANCE/OUTLET TIRE WASH

WIND EROSION CONTROL

WE1-WIND EROSION CONTROL

NON-STORMWATER MANAGEMENT NS1-WATER CONSERVATION PRACTICES NS2-DEWATERING OPERATIONS NS3-PAVING AND GRINDING OPERATIONS NS4 TEMPORARY STREAM CROSSING NS5 CLEAR WATER DIVERSION NS6-ILLICIT CONNECTION/DISCHARGE NS7-POTABLE WATER/IRRIGATION NS8 VEHICLE AND EQUIPMENT CLEANING NS9 VEHICLE AND EQUIPMENT FUELING NS10 VEHICLE AND EQUIPMENT MAINTENANCE NS11-PILE DRIVING OPERATIONS NS12-CONCRETE CURING NS13-CONCRETE FINISHING NS14 MATERIAL OVER WATER NS15 DEMOLITION ADJACENT TO WATER NS16-TEMPORARY BATCH PLANTS

WASTE MANAGEMENT & MATERIALS POLLUTION CONTROL

WM10-LIQUID WASTE MANAGEMENT

WM1-MATERIAL DELIVERY AND STORAGE WM2-MATERIAL USE WM3-STOCKPILE MANAGEMENT WM4-SPILL PREVENTION AND CONTROL WM5-SOLID WASTE MANAGEMENT WM6-HAZARDOUS WASTE MANAGEMENT WM7-CONTAMINATED SOIL MANAGEMENT WM8-CONCRETE WASTE MANAGEMENT WM9-SANITARY/SEPTIC WASTE MANAGEMENT

EROSION CONTROL NOTES:

- TEMPORARY EROSION CONTROL DEVICES SHOWN ON THE GRADING PLAN WHICH INTERFERE WITH THE WORK SHALL BE RELOCATED OR MODIFIED AS AND WHEN THE INSPECTOR SO DIRECTS AS THE WORK PROGRESSES TO MEET "AS GRADED" CONDITIONS.
- 2. ALL LOOSE SOIL AND DEBRIS SHALL BE REMOVED FROM THE STREET AREAS UPON STARTING OPERATIONS AND PERIODICALLY THEREAFTER AS DIRECTED BY THE **INSPECTOR**
- WHEN THE INSPECTOR SO DIRECTS, A 12-INCH BERM SHALL BE MAINTAINED ALONG THE TOP OF THE SLOPE OF THOSE FILLS ON WHICH GRADING IS NOT IN PROGRESS.
- 4. STORM AND SEWER DRAIN TRENCHES THAT ARE CUT THROUGH BASIN DIKES OR BASIN INLET DIKES SHALL BE PLUGGED WITH SANDBAGS.
- 5. EXCEPT WHEN THE INSPECTOR DIRECTS OTHERWISE, ALL DEVICES SHOWN SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN RAIN IS FORECAST, AND SHALL BE MAINTAINED DURING THE RAINY SEASON (OCTOBER 15 TO APRIL 15).
- 6. SANDBAGS SHALL BE STOCKPILED ON SITE, READY TO BE PLACED IN POSITION WHEN RAIN IS FORECAST, OR WHEN THE INSPECTOR SO DIRECTS.
- 7. A "STANDBY EMERGENCY CREW" SHALL BE ALERTED BY THE PERMITTEE OR THE CONTRACTOR TO PERFORM EMERGENCY WORK DURING RAINSTORMS. THE PARTY TO BE CONTACTED IS:

._____ (TO BE FILLED IN BY CONTRACTOR) PHONE NUMBER:

DUST CONTROL NOTES:

- 1. DUST SHALL BE CONTROLLED BY WATERING AND/OR APPLYING A DUST PALLIATIVE. THE DUST PALLIATIVE SHALL BE APPLIED IN THE AMOUNT AT THE LOCATIONS AS DIRECTED BY THE ENGINEER.
- 2. WATER FOR DUST CONTROL SHALL BE APPLIED BY MEANS OF PRESSURE TYPE DISTRIBUTORS OR PIPE LINES EQUIPPED WITH A SPRAY SYSTEM OR HOSES WITH NOZZLES THAT WILL ENSURE A UNIFORM APPLICATION OF WATER.
- 3. UNLESS WATER IS APPLIED BY MEANS OF PIPE LINES, AT LEAST ONE MOBILE UNIT WITH A MINIMUM CAPACITY OF 100 GALLONS SHALL BE AVAILABLE FOR APPLYING
- 4. ALL SOIL MATERIALS OR DEBRIS TRUCKED FROM THE SITE SHALL BE COVERED AND SPRINKLED PRIOR TO ENTERING PUBLIC STREETS.
- 5. PROVIDE FOR WET SUPPRESSION OR CHEMICAL STABILIZING OF EXPOSED SOILS.
- 6. PROVIDE FOR RAPID CLEAN-UP OF SEDIMENTS DEPOSITED ON THE PAVED ROADS.
- 7. LIMIT THE AMOUNT OF AREAS DISTURBED BY CLEARING & EARTH MOVING OPERATIONS BY SCHEDULING THESE ACTIVITIES IN PHASES.

EROSION CONTROL NOTES:

- (E1) PLACE GRAVEL BAGS TRIPLE ROW PER DETAIL 1, HEREON.
- (E2) STABILIZED CONSTRUCTION ENTRANCE PER DETAIL 2, HEREON.

LEGEND


LIMIT OF WORK

PROPERTY LINE



DIRECTION OF FLOW

PROTECT TREE IN PLACE



EROSION CONTROL PLAN




integrated construction management sustainability






700 South Flower Street Suite 2100 Los Angeles, CA 90017 O: 213.418.0201 F: 213.266.5294 www.kpff.com






integrated design construction management sustainability





700 South Flower Street Suite 2100 Los Angeles, CA 90017 O: 213.418.0201 F: 213.266.5294 www.kpff.com


O HELP EVERYONE
LENNOX CLINIC
10223 FIRMONA AVE.



12/14/2018 01/29/2019 02/15/2019 03/11/2019 -

GRADING PLAN

C1.3



<u>IOTE:</u>

IRRIGATION WATER METER, LINES AND APPURTENANCES BY OTHERS.

NOTE:

ALL BMP'S PROPOSED AS A PART OF THIS PROJECT ARE TO BE INSPECTED BY THE ENGINEER OF RECORD AFTER INSTALLATION AND PRIOR TO OBTAINING A CERTIFICATE OF OCCUPANCY.

NOTE:

PRIOR TO THE INSTALLATION OF ALL STORM DRAIN AND SEWER MAIN LINE CONNECTIONS, THE CONTRACTOR SHALL POTHOLE AND VERIFY THE HORIZONTAL AND VERTICAL LOCATION OF THE MAIN LINE. IF CONDITIONS DIFFER FROM THOSE ON THE PLAN, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND SHALL NOT BEGIN CONSTRUCTION UNTIL THE CHANGED CONDITION HAS BEEN EVALUATED.

UTILITY CONSTRUCTION NOTES:

STORM DRAIN

- SD1) PVC, SDR-35 STORM DRAIN PIPE PER DETAIL 1, SHEET C5.0. SIZE AND SLOPE PER PLAN.
- SD2) POINT OF CONNECTION 5 FEET FROM BUILDING FACE. SEE PLUMBING DRAWINGS FOR CONTINUATION.
- (SD3) CLEANOUT. PER DETAIL 2, SHEET C5.0.
- SD4) AREA DRAIN, PER DETAIL 3, SHEET C5.0.
- SD5 PRECAST CONCRETE CATCH BASIN. JENSEN PRECAST PRODUCTS OR APPROVED EQUIVALENT. SIZE AND GRATE BEARING TYPE PER PLAN.
- (SD6) STORMWATER TREATMENT UNIT. PER DETAIL [___], SHEET [___].

SANITARY SEWER

- SS1) PVC, SDR-35 SANITARY SEWER PIPE PER DETAIL [___]. SIZE AND SLOPE PER PLAN.
- POINT OF CONNECTION 5 FEET FROM BUILDING FACE. SEE PLUMBING DRAWINGS FOR CONTINUATION.
- (\$S3) CLEANOUT. PER DETAIL [___], SHEET [___].
- (\$\$4) PRECAST CONCRETE MANHOLE PER APWA STANDARD PLAN 200-2.

DOMESTIC WATER

- W1 PVC C-900 DOMESTIC WATER PIPE PER DETAIL [___], SHEET [___]. SIZE PER PLAN.
- W2 POINT OF CONNECTION 5 FEET FROM BUILDING FACE. SEE PLUMBING DRAWINGS FOR CONTINUATION.
- (W3) BACKFLOW PREVENTION DEVICE. PER DETAIL [___], SHEET [___].
- W4 WATER METER VAULT. INSTALLATION BY [LOCAL WATER PROVIDER, CONTRACTOR]. SHOWN FOR COORDINATION PURPOSES ONLY. CONTRACTOR TO COORDINATE WATER SERVICE CONNECTION WITH LOCAL PROVIDER.

FIRE WATER

- F1 PVC C-900 FIRE WATER PIPE PER DETAIL [___], SHEET [___]. SIZE AND MATERIAL PER PLAN.
- POINT OF CONNECTION 5 FEET FROM BUILDING FACE. SEE PLUMBING DRAWINGS FOR CONTINUATION.
- F3 BACKFLOW PREVENTION DEVICE. PER DETAIL [___], SHEET [___].
- WATER METER VAULT. INSTALLATION BY [LOCAL WATER PROVIDER, CONTRACTOR]. SHOWN FOR COORDINATION PURPOSES ONLY. CONTRACTOR TO COORDINATE FIRE WATER SERVICE CONNECTION WITH LOCAL PROVIDER.
- F5 FIRE HYDRANT. PER DETAIL [___], SHEET [___].
- (F6) FIRE DEPARTMENT CONNECTION.

LIMIT OF WORK

F7 POST INDICATOR VALVE.

OTHER UTILITIES

- U1 ELECTRICAL CONDUIT. SEE ELECTRICAL DRAWINGS FOR DETAILS AND SPECIFICATIONS. SHOWN FOR COORDINATION PURPOSES ONLY.
- U2 GAS LINE. SEE GAS COMPANY DRAWINGS FOR DETAILS AND SPECIFICATIONS. SHOWN FOR COORDINATION PURPOSES ONLY.
- MECHANICAL LINE. SEE MECHANICAL DRAWINGS FOR DETAILS AND SPECIFICATIONS. SHOWN FOR COORDINATION PURPOSES ONLY.

LEGEND:

	LIMIT OF WORK
	PROPERTY LINE
ss	SANITARY SEWER
w	WATER
DW	DOMESTIC WATER
——FW——	FIRE WATER
SD	STORM DRAIN
——-G——	GAS
——Е——	ELECTRIC
т	TELEPHONE
	PERFORATED PIPE
-	POINT OF CONNECTION
 \$	COORDINATION POINT
 3	CAP OR PLUG
	UTILITY MANHOLE
(<u>o</u>)	UTILITY CLEANOUT
	STORM DRAIN INLET
⊕	AREA DRAIN/PLANTER DRAIN
	TRENCH DRAIN
	FIRE HYDRANT
	THRUST BLOCK
8	FIRE DEPARTMENT CONNECTION (FDC)

POST INDICATOR VALVE (PIV)


WATER VALVE

BACKFLOW ASSEMBLY

UTILITY METER VAULT



integrated design construction management sustainability



kpff

700 South Flower Street Suite 2100 Los Angeles, CA 90017 O: 213.418.0201 F: 213.266.5294 www.kpff.com

HELP EVERYONE
LENNOX CLINIC
3223 FIRMONA AVE.
FINOX CA 90304


•												
,												
	1	1	ı	ı	ı	ı	ļ	ı	ı	ı	ı	

DESIGN DEVELOPMENT
FINISHES PRESENTATION
30% CONSTRUCTION DOCUMENTS
50% CONSTRUCTION DOCUMENTS
PLAN CHECK SUBMITTAL
-

12/14 61/29, 62/15, 63/11, 63/29,

UTILITY PLAN

C1.4



PAVING CONSTRUCTION NOTES

- (PO1) CONCRETE CURB. PER DETAIL X, SHEET C5.X.
- PO2) CONCRETE CURB AND GUTTER. PER DETAILX, SHEET C5.X.
- (P03) DECOMPOSED GRANITE. SEE ARCHITECTURAL PLANS FOR DETAILS.
- PO4) ASPHALT CONCRETE PAVEMENT. PER DETAIL X, SHEET C5.X.
- (PO5) CONCRETE PAVEMENT. PER DETAIL 4 ON SHEET C5.0.
- (P06) STAIRS. SEE ARCHITECTURAL PLANS FOR DETAILS.
- (P07) WATER HEATER ENCLOSURE. SEE ARCHITECTURAL PLANS FOR DETAILS.
- (P08) WASTE ENCLOSURE. SEE ARCHITECTURAL PLANS FOR DETAILS.

LEGEND

PROPERTY LINE CONCRETE PAVING

(REFER TO SHEET C5.0 FOR DETAILS)

(REFER TO SHEET [CX.XX] FOR DETAILS)

DECOMPOSED GRANITE (REFER TO ARCHITECTURAL PLANS FOR DETAILS)


PLANTER AREA/LANDSCAPE (REFER TO LANDSCAPING PLANS FOR DETAILS)

NOTE TO CONTRACTOR/CONSTRUCTION SURVEYOR:

CONSTRUCTION STAKING FOR IMPROVEMENTS SHOWN ON THESE PLANS SHALL BE PERFORMED BY A LICENSED LAND SURVEYOR. CONSTRUCTION STAKING SURVEYOR SHALL BE RESPONSIBLE FOR COORDINATION OF THESE PLANS WITH SOURCE DRAWINGS PREPARED BY ARCHITECT, LANDSCAPE ARCHITECT, STRUCTURAL ENGINEER, MEP CONSULTANT AND ANY OTHER DISCIPLINE PRIOR TO START OF STAKING AND CONSTRUCTION. ANY DISCREPANCIES THAT OCCUR SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO THE START OF CONSTRUCTION SO THAT A CLARIFICATION CAN BE ISSUED.




integrated d e s i g n construction management şustajnability



700 South Flower Street Suite 2100 Los Angeles, CA 90017 O: 213.418.0201 F: 213.266.5294 www.kpff.com

PAVING PLAN



N.T.S. 2 STANDARD CLEANOUT

4 | CONCRETE WALK SECTION

integrated design construction management şustajnability



N.T.S.

700 South Flower Street Suite 2100 Los Angeles, CA 90017 O: 213.418.0201 F: 213.266.5294

www.kpff.com

 $O \square$

CIVIL DETAILS

N.T.S. 1 | FLEXIBLE PIPE BEDDING DETAIL